## ADDENDUM #3 TO SPEC. 05-058

# Pine Lake Road Widening 40<sup>th</sup> to 60<sup>th</sup> Street from Thompson Creek to Shadow Pines CIP 700014

Addendum #3 to Spec. 05-058 for above project to be opened on **Wednesday, March 16, 2005 at 12:00 noon**.

All prospective bidders are to go to the website and download all addendums and acknowledge receipt in the bid submittal document.

Website: http://www.lincoln.ne.gov/city/finance/purch/spec/index.htm

Dated this 14<sup>th</sup> day of March, 2005.

Purchasing Department

Mary L. Long Assistant Purchasing Agent

# ADDENDUM #3 TO SPEC. 05-058

March 14, 2005

Pine Lake Road Widening 40<sup>th</sup> to 61<sup>st</sup> Street & S. 56<sup>th</sup> Street from Thompson Creek Blvd. To Shadow Pines Drive.

The state of the s

-----

Addendum #3 to Spec. 05-058 for above project to be opened on Wednesday, March 16, 2005 at 12:00 noon. Any and all additional questions need to be in writing to Mary Long in the Purchasing Department by noon, Monday, March 14, 2005. No questions will be answered after this time. Mary's fax number is 441-6513 or her e-mail is mlong@lincoln.ne.gov.

The following questions have been asked:

- 1. Is the City going to enforce property owner agreements to remove fencing, so that the Contractor may expect not to incur costs relating to the removal of this property? The City has told homeowners that it is their responsibility to remove the fence and landscape materials in accordance with their right-of-way/easement agreements. The homeowners have been told that they will receive a door hanger two to three weeks prior to the fence or landscape items needing to be moved. If the fence/landscape is not moved by the time the Contractor needs the land, then the Contractor will be directed by the Engineer to take ownership of the fence/landscape and remove it from the project site. If the Contractor needs to remove the fence/landscape items, then a payment price will be negotiated during construction.
- Does the reinforcing steel for the retaining walls need to be epoxy coated?
   Yes. All reinforcing steel for retaining walls shall be epoxy coated and paid for using bid item 08.0015, "Reinforcing Steel for Retaining Walls (In Place)"
- 3. Can Lincoln Electric System work more than a regular 5 day work week? (From pre-bid meeting)

Lincoln Electric System will do what they can to help the situation, but Lincoln Electric System is not a party to the contract between the City and the Contractor.

4. Does Lincoln Electric System have a plan (construction schedule)? (From pre-bid meeting)

Lincoln Electric System will furnish a construction schedule when their work order is written and approved (early April). They will coordinate their work with the Contractor while maintaining service to existing customers.

Addendum #3 to Spec 05-058 Pine Lake Road Widening, 40<sup>th</sup> to 61<sup>st</sup> March 14, 2005

- 5. Will the 4" PVC Slotted Drain Pipe and Compacted 47B sand gravel, as detailed on page 103, be required behind the wall where LES poles are located, according to sheet 186?

  The subdrains can be modified during construction to tie into the nearest storm drainage structure.
- 6. What is the correct stationing on sheet 57 of wall #13? The station range should be 138+00 to 142+00.
- 7. At some locations it will be tight to safely construct the retaining walls. Will the sheet piling be subsidiary to the bid items for retaining wall construction?

  Sheet piling will be necessary to construct the retaining walls at some locations. Sheet piling is included in the Bidding Schedule on page 4. The quantity has been increased as part of this Addendum.
- 8. How are the retaining walls to be formed in the areas detailed on sheet 186? Can this area use tight sheet piling as the backside form?

Forming the retaining wall at this location is at the discretion of the Contractor. No additional payment will be made for tight sheet piling.

9. Where will the topsoil on the summary sheet be placed?
6" of topsoil shall be placed at disturbed soil locations behind the back of curb and 12" of topsoil shall be placed in the medians as shown on the typical sections. The topsoil on site shall be stockpiled for later placement, but topsoil will need to be brought in from off site to balance the quantity.

A revised Bidding Schedule is included as part of Addendum #3. Please replace the Bidding Schedule from Addendum #2 with the revised Bidding Schedule. A summary of the Bidding Schedule modifications are listed in this addendum for your information.

#### **BIDDING SCHEDULE MODIFICATIONS:**

- Page 3: Delete Item No. 03.0060 "9" Portland Cement Conc. Pav't w/Integral Curb."
- Page 3: Add Item No. 50.0040 "9" Doweled Portland Cement Conc. Pav't w/Integral Curb", Quantity = 91,245 S.Y.
- Page 3: Item No. 07.0020 Change the quantity for the pay item "Concrete Sidewalk 4" Thick" from 104,515 S.F. to 105,187 S.F.
- Page 4: Item No. 50.0005 Change the quantity for the pay item "Sheet Piling (8' Sheets) For Construction Protection" from 100 L.F. to 1000 L.F.
- Page 7: Add Item No. 21.0040 "54" R.C.P. Storm Sewer, Class III", Quantity = 304 L.F.
- Page 7: Item No. 21.0050 Change the quantity for the pay item "48" R.C.P. Storm Sewer, Class III" from 958 L.F. to 654 L.F.

- Page 7: Item No. 21.0070 Change the quantity for the pay item "36" R.C.P. Storm Sewer, Class III" from 1490 L.F. to 1960 L.F.
- Page 7: Item No. 21.0080 Change the quantity for the pay item "30" R.C.P. Storm Sewer, Class III" from 1734 L.F. to 1399 L.F.
- Page 7: Item No. 21.0090 Change the quantity for the pay item "24" R.C.P. Storm Sewer, Class III" from 521 L.F. to 728 L.F.
- Page 8: Item No. 21.0095 Change the quantity for the pay item "21" R.C.P. Storm Sewer, Class III" from 1514 L.F. to 1448 L.F.
- Page 8: Item No. 21.0100 Change the quantity for the pay item "18" R.C.P. Storm Sewer, Class III" from 2819 L.F. to 2749 L.F.
- Page 8: Item No. 21.0110 Change the quantity for the pay item "15" R.C.P. Storm Sewer, Class III" from 2506 L.F. to 2408 L.F.
- Page 8: Item No. 21.0560 Change the quantity for the pay item "36" R.C. Flared End Section" from 1 Ea. to 2 Ea.
- Page 8: Delete Item No. 21.0590 "24" R.C. Flared End Section"
- Page 8: Delete Item No. 21.0620 "15" R.C. Flared End Section"
- Page 8: Item No. 21.0870 Change the quantity for the pay item "Storm Sewer Manhole, 54"-60" (Complete)" from 1 Ea. to 3 Ea.
- Page 9: Item No. 21.0880 Change the quantity for the pay item "Storm Sewer Manhole, 48" (Complete)" from 6 Ea. to 4 Ea.
- Page 9: Item No. 21.0890 Change the quantity for the pay item "Storm Sewer Manhole, 36" (Complete)" from 5 Ea. to 7 Ea.
- Page 9: Item No. 21.0895 Change the quantity for the pay item "Storm Sewer Manhole, 15"-30" (Complete)" from 26 Ea. to 24 Ea.
- Page 9: Item No. 21.2090 Change the quantity for the pay item "Geotextile Filter Fabric (In Place)" from 194 S.Y. to 188 S.Y.
- Page 9: Item No. 21.2111 Change the quantity for the pay item "Rip-Rap (In Place)" from 140 Tons to 124 Tons.
- Page 10: Item No. 23.0080 Change the quantity for the pay item "6" D.I. Pipe Water Main, Cl 52 (Polywrapped)" from 288 L.F. to 338 L.F.

Page 10: Item No. 23.1100 Change the quantity for the pay item "Remove Hydrant (Complete)" from 9 Ea. to 10 Ea.

Page 10: Delete Item No. 23.0450 "8" Gate Valve, M.J."

Page 10: Item No. 23.0460 Change the quantity for the pay item "6" Gate Valve, M.J." from 10 Ea. to 11 Ea.

Page 10: Item No. 23.0492 Change the quantity for the pay item "Hydrant, Complete L=6.5" from 1 Ea. to 2 Ea.

Page 11: Add Item No. 23.0570 "24" x 6" Tee, M.J.", Quantity = 1 Ea.

Page 11: Item No. 23.0594 Change the quantity for the pay item "6" Anchoring Coupling, M.J. (L=18")" from 3 Ea. to 5 Ea.

#### **PLAN SHEET MODIFICATIONS:**

Plan Sheets 2 and 3: Modifications to item descriptions, units, or quantities as noted above in the revised Bidding Schedule will also be modified on the Schedule of Approximate Quantities plan sheets in the bid plan set. In addition to the Bidding Schedule modifications, the following corrections have been made:

Plan Sheet 55: Change the Quantity for Pipe D3 From 215 L.F. to 250 L.F.

Plan Sheet 56: Change the Size For Pipe E3 From 27" to 30".

Plan Sheet 57: Change the station range for wall #13 to "138+00 to 142+00."

Plan Sheet 68: Add the Build Note for "Build Concrete Median Surfacing 4" Thick", Build Number: 2, Quantity: 2,510 S.F.

Plan Sheet 72: Change the Size For F.E.S. V2 From 24" to 21".

Plan Sheet 98: Delete Note and Symbol For "Raised 24" Water Main"

Addendum #3 to Spec 05-058 Pine Lake Road Widening, 40<sup>th</sup> to 61<sup>st</sup> March 14, 2005

### **SPECIAL PROVISION MODIFICATIONS:**

Add the following section to the Special Provisions:

#### DOWELED PORTLAND CEMENT CONCRETE WITH INTEGRAL CURB

The Contractor shall construct doweled P.C.C.P. of the thickness specified on the plans or at locations directed by the Engineer. Dowels will be required at all transverse joints, regardless of the joint spacing, in the through traffic lanes of Pine Lake Road and 56<sup>th</sup> Street. All doweled pavement shall be constructed in accordance with the pertinent requirements stipulated in Sections 603, 1021, and 1022 of the State of Nebraska Department of Roads stipulated in Specifications for Highway Construction including the July 21, 2001 Supplemental Specifications. Concrete for the 9" Doweled P.C.C.P. shall be in accordance with the City of Lincoln's Standard Specifications for Municipal Construction, and the 2004 Supplemental Specifications to the Standard Specifications for Municipal Construction.

Doweled P.C.C.P. with Integral Curb shall be measured and paid for by the square yard of pavement constructed and accepted by the Engineer.

## **Project Items**

Item Num	ber Quantity	Unit	Unit Price	Extension
	Section	n: 1 R	emovals	
01.0100	12,062.000	C.Y.	\$	\$
	Pavement & Sidewalk Removal		<u> </u>	
01.0210	500.000	L.F.	\$	\$
	Type "A" Sawing		<u> </u>	
01.0220	3,541.000	L.F.	\$	\$
	Type "B" Sawing			
01.0230	133.000	L.F.	\$	\$
	Type "C" Sawing			
02.0010	1.000	L.S.	\$	\$
	General Clearing & Grubbing		<u> </u>	
02.0020	25.000	Ea.	\$	\$
	Tree Removal (12" to 23")			
			Section 1	Γotal: \$
	Section: 2 Pavemen	nt and	Miscellaneous Ite	ms
01.0040	5,988.000	S.Y.	\$	\$
	Asph. Conc. Pav't, Class 2 (6" Bas	se)	<u> </u>	
50.0035	500.000	Ton	\$	\$
	Temporary Asphalt			
01.0140	737.000	Ton	\$	\$
	Asph. Conc. Surface Course, For A	Arterial	Street	
01.0170	12.000	Ea.	\$	\$
	Adjust Manhole to Grade, Complete	te	L.,	
01.0180	18.000	Ea.	\$	\$
	Adjust Water Valve Box To Grade,	Compl	lete	
01.0190	13.000	Ea.	\$	\$
	Standard Monument Box (In Place	•)		

Item Numb	per Quantity	Unit	Unit Price	Extension
02.0110	93,356.000	C.Y.	\$	\$
	Earth Borrow Measured in Embar	ıkment	(E.Q.)	
06.0050	24.000	Ea.	\$	\$
	Concrete Median Nose, (In Place)	)		
06.0060	41,297.000	S.F.	\$	\$
	Concrete Median Surfacing, 4" Th	ick		
07.0020	105,187.000	S.F.	\$	\$
	Concrete Sidewalk, 4" Thick			
07.0040	5,219.000	S.F.	\$	\$
	Concrete Driveway, 5" Thick			
08.0015	129,185.000	Lb.	\$	\$
	Reinforcing Steel for Retaining Wa	alls (In	Place)	
08.0020	1,436.000	C.Y.	\$	\$
	Concrete for Retaining Walls (In P	lace)		
08.0025	3,044.000	S.F.	\$	\$
	Modular Block Retaining Wall			
09.0070	1,588.000	L.F.	\$	\$
	48" Pipe Railing Fence (In Place)			
10.0010	300.000	Ton	\$	\$
	Crushed Rock Surfacing (In Place	)		
30.0010	240,150.000	S.F.	\$	\$
	Sodding, Complete			
30.0090	12.900	Ac.	\$	\$
	Seeding, Type "D"			
32.0010	115.000	Bale	\$	\$
	Straw Bale Dike Installation			
32.0020	115.000	Bale	\$	\$
	Straw Bale Dike Maintenance			

Item Numb	per Quantity	Unit	Unit Price	Extension			
32.0030	115.000	Bale	\$	\$			
	Straw Bale Dike Removal	٠		**************************************			
32.0040	7,405.000	L.F.	\$	\$			
	Synthetic Fabric Silt Fence Install	ation					
32.0050	7,405.000	L.F.	\$	\$			
	Synthetic Fabric Silt Fence Mainte	enance					
32.0060	7,405.000	L.F.	\$	\$			
	Synthetic Fabric Silt Fence Removal						
32.0070	96.000	Ea.	\$	\$			
	Install Storm Drain Inlet Protection						
32.0080	96.000	Ea.	\$	\$			
	Storm Drain Inlet Protection Maintenance						
32.0090	96.000	Ea.	\$	\$			
	Remove Storm Drain Inlet Protection						
50.0040	8,975.000	S.Y.	\$	\$			
	Install Type I Erosion Control Mat						
50.0040	8,975.000	S.Y.	\$	\$			
	Type I Erosion Control Mat Mainte	nance					
50.0005	1,000.000	L.F.	\$	\$			
	Sheet Piling (8' Sheets) For Const	ruction	Protection				
50.0045	69,128.000	S.F.	\$	<b> </b>   <b> </b>   <b> </b>			
	Buffalo Grass Plugs						
50.0020	8.000	Ac.	\$	\$			
	Cover Crop		<u> </u>				
50.0015	1.000	L.S.	\$	\$			
	Construction Staking						
50.0015	1.000	L.S.	\$	\$			
	Traffic Control						

Item Num	ber Quantity	Unit	Unit Price	Extension
50.0015	1.000 Mobilization	L.S.	\$	\$
50.0001	24.000 Ground Sleeve	Ea.	\$	\$
50.0045	900.000 Detectable Warning Panel	S.F.	\$	\$
50.0010	427.000 Compost	C.Y.	\$	\$
50.0040	91,245.000 Misc 9" Doweled Portland Cemen		\$ Pav't w/Integral Curb	\$
			Section 2 Tota	l: \$
	Section	on: 3 M	arkings	
13.0270	10,378.000 Paint Marking, 4" Yellow	L.F.	\$	\$
13.0275	10,751.000 Paint Marking, 4" White	L.F.	\$	\$
13.0280	10,673.000 Paint Marking, 8" White	L.F.	\$	\$
13.0305	3,758.000 Paint Marking, 12" White	L.F.	\$	\$
13.0300	424.000 Paint Marking, 12" Yellow	L.F.	\$	\$
13.0530	70.000 Remove Paint Marking, 4"	L.F.	\$	\$
13.0532	190.000 Remove Paint Marking, 8"	L.F.	\$	\$
13.0533	400.000 Remove Paint Marking, 12"	L.F.	\$	\$

per Quantity	Unit	Unit Price	Extension			
60.000	Ea.	\$	\$			
Raised Pavement Markers						
<del></del>		Section 3	Total: \$			
Section: 4 S	torm E	Prainage Items				
55.000	L.F.	\$	\$			
30" C.M.P. Storm Sewer, 16 Gaug	ge					
1.000	Ea.	\$	\$			
30" x 45 Degree C.M. Bend, 16 Gauge						
1.000	Ea.	\$	\$			
30" C.M. F.E.S., 16 Gauge						
150.000	L.F.	\$	\$			
Remove 38" x 60" Elliptical Pipe						
2.000	Ea.	\$	\$			
Remove R.C. Box, Wingwalls & Headwalls (Complete)						
1.000	Ea.	\$	\$			
Remove 38" x 60" Elliptical Flared	End S	ection				
186.000	L.F.	\$	\$			
Remove 42" Storm Sewer Pipe		L				
170.000	L.F.	\$	\$			
Remove 36" Storm Sewer Pipe		<u> </u>				
174.000	L.F.	\$	\$			
Remove 30" Storm Sewer Pipe						
1,098.000	L.F.	\$	\$			
Remove 24" Storm Sewer Pipe		L				
475.000	L.F.	\$	\$			
Remove 18" Storm Sewer Pipe						
117.000	L.F.	\$	\$			
Remove 15" Storm Sewer Pipe		<u> </u>				
	Section: 4 S  Section: 4 S  55.000 30" C.M.P. Storm Sewer, 16 Gauge  1.000 30" x 45 Degree C.M. Bend, 16 G  1.000 30" C.M. F.E.S., 16 Gauge  150.000 Remove 38" x 60" Elliptical Pipe  2.000 Remove R.C. Box, Wingwalls & H  1.000 Remove 38" x 60" Elliptical Flared  186.000 Remove 42" Storm Sewer Pipe  170.000 Remove 36" Storm Sewer Pipe  174.000 Remove 30" Storm Sewer Pipe  1,098.000 Remove 24" Storm Sewer Pipe  475.000 Remove 18" Storm Sewer Pipe	Section: 4 Storm   Ea.	Raised Pavement Markers   Section 3			

Item Numb	er Quantity	Unit	Unit Price	Extension		
21.1610	2.000	Ea.	\$	\$		
	Remove 48" R.C. Flared End Sec	tion				
21.1620	2.000	Ea.	\$	\$		
	Remove 42" R.C. Flared End Sect	tion				
21.1640	1.000	Ea.	\$	\$		
	Remove 30" R.C. Flared End Sect	tion				
21.1650	12.000	Ea.	\$	\$		
	Remove 24" R.C. Flared End Sect	ion				
21.1670	5.000	Ea.	\$	\$		
	Remove 18" R.C. Flared End Sect	ion				
21.1680	1.000	Ea.	\$	\$		
	Remove 15" R.C. Flared End Section					
21.1700	1.000	Ea.	\$	\$		
	Remove Storm Sewer Manhole (C	omplet	te)			
21.1710	11.000	Ea.	\$	\$		
	Remove Existing Inlet (Complete)					
21.1750	3.000	Ea.	\$	\$		
	Remove Existing Headwall (Comp	lete)				
21.0030	220.000	L.F.	\$	\$		
	60" R.C.P. Storm Sewer, Class III					
21.0040	304.000	L.F.	\$	\$		
	54" R.C.P. Storm Sewer, Class III					
21.0050	654.000	L.F.	\$	\$		
***************************************	48" R.C.P. Storm Sewer, Class III					
21.0070	1,960.000	L.F.	\$	\$		
	36" R.C.P. Storm Sewer, Class III					
21.0080	1,399.000	L.F.	\$	\$		
	30" R.C.P. Storm Sewer, Class III					

Item Numb	er Quantity	Unit	Unit Price	Extension
21.0090	728.000	L.F.	\$	\$
	24" R.C.P. Storm Sewer, Class III			
21.0095	1,448.000	L.F.	\$	\$
	21" R.C.P. Storm Sewer, Class III		<u></u>	
21.0100	2,749.000	L.F.	\$	\$
	18" R.C.P. Storm Sewer, Class III			
21.0110	2,408.000	L.F.	\$	\$
	15" R.C.P. Storm Sewer, Class III			
21.0560	2.000	Ea.	\$	\$
٠	36" R.C. Flared End Section			
21.0570	1.000	Ea.	\$	\$
	30" R.C. Flared End Section			
21.0600	1.000	Ea.	\$	\$
	21" R.C. Flared End Section			
21.0610	1.000	Ea.	\$	\$
	18" R.C. Flared End Section			
21.0770	21.000	Ea.	\$	\$
	72" Storm Sewer Inlet (Complete)			
21.0780	63.000	Ea.	\$	\$
	72" Canted Storm Sewer Inlet (Cor	nplete)		
21.0790	4.000	Ea.	\$	\$
	72" Radius Storm Sewer Inlet (Con	nplete)	<u> </u>	
21.0830	7.000	Ea.	\$	\$
	Grate Inlet, Type "F-2" (Complete)			
21.0870	3.000	Ea.	\$	\$
	Storm Sewer Manhole, 54"-60" (Co	mplete	e)	
21.0880	4.000	Ea.	\$	\$
	Storm Sewer Manhole, 42"-48" (Co	mplete	e)	

Item Num	ber Quantity	Unit	Unit Price	Extension				
21.0890	7.000	Ea.	\$	\$				
	Storm Sewer Manhole, to 36" (Co	mplete	)					
21.0895	24.000	Ea.	\$	\$				
	Storm Sewer Manhole, 15" - 30" (	Storm Sewer Manhole, 15" - 30" (Complete)						
21.0940	7.000	C.Y.	\$	\$				
<u></u>	Concrete for Collars, Elbows & He	Concrete for Collars, Elbows & Headwalls (In Place)						
21.0950	567.000	Lb.	\$	\$				
	Reinf. Steel for Collars, Elbows &	Reinf. Steel for Collars, Elbows & Hdwls (In Place)						
21.1850	160.000	L.F.	\$	\$				
	4' R.C. Low Flow Liner							
21.2090	188.000	S.Y.	\$	\$				
	Geotextile Filter Fabric (In Place)							
21.2111	124.000	Ton	\$	\$				
	Rip-Rap (In Place)							
21.0930	31,800.000	Lb.	\$	\$				
	Reinf. Steel for Structures (In Place	e)						
21.0920	306.000	C.Y.	\$	\$				
	Concrete for Structures (In Place)							
			Section 4 Tota	ıl: \$				
	Section	: 5 Wa	ter Items					
23.0950	130.000	L.F.	\$	\$				
	Remove 6" Water Main							
23.0930	220.000	L.F.	\$	\$				
	Remove 12" Water Main	•		L				
23.0900	1,771.000	L.F.	\$	\$				
	Remove 24" Water Main							
23.1100	10.000	Ea.	\$	<b>\$</b>				
	Remove Hydrant (Complete)	-						

Item Numb	oer Quar	ntity	Unit	Unit Price	Extension
23.0080	338.	.000	L.F.	\$	\$
	6" D.I. Pipe Water Main, CI 5	2 (Pol	ywrap	ped)	
23.0070	80.	000	L.F.	\$	\$
	8" D.I. Pipe Water Main, Cl 5	2 (Pol	ywrap	ped)	
23.0060	650.	000	L.F.	\$	\$
	12" D.I. Pipe Water Main, Cl	52 (Po	olywra	pped)	
23.0030	1,801.	000	L.F.	\$	\$
24" D.I. Pipe Water Main, Cl 52 (Polywrapped)					d (
23.0120	1.	000	Ea.	\$	\$
	24" x 8" Tapping Sleeve & Va	alve, N	/l.J.	<u> </u>	
23.0110	5.	000	Ea.	\$	\$
	24" x 12" Tapping Sleeve & \	/alve,	M.J.		
23.0460	11.	000	Ea.	\$	\$
	6" Gate Valve, M.J.			1	J []
23.0490	9.	000	Ea.	\$	\$
	Hydrant, Complete L=5.5'				J
23.0492	2.	000	Ea.	\$	\$
	Hydrant, Complete L=6.5'			•	J (
23.0538	1.	000	Ea.	\$	\$
	6" X 90 Deg. Bend, M.J.			-	
23.0540	. 8.	000	Ea.	\$	\$
	24" X 45 Deg. Bend, M.J.				
23.0544	8.0	000	Ea.	\$	\$
	12" X 45 Deg. Bend, M.J.				J []
23.0546	9.0	000	Ea.	\$	\$
	6" X 45 Deg. Bend, M.J.				J
23.0560	3.0	000	Ea.	\$	\$
	12" X 11.25 Deg. Bend, M.J.			<u> </u>	1

Item Numb	er Quantity	Unit	Unit Price	Extension
23.0570	1.000	Ea.	\$	\$
	24" X 6" Tee, M.J.			NAAA NAAA AAAA AAAA AAAA AAAA AAAA AAA
23.0583	1.000	Ea.	\$	\$
	8" X 6" Tee, M.J.			
23.0644	4.000	Ea.	\$	\$
	24" Solid Sleeve, M.J. (L=15")			
23.0648	4.000	Ea.	\$	\$
	12" Solid Sleeve, M.J. (L=12")			
23.0651	4.000	Ea.	\$	<b>s</b>
	6" Solid Sleeve, M.J. (L=18")		<u> </u>	
23.0592	1.000	Ea.	\$	\$
	6" Anchoring Elbow, M.J.			
23.0594	5.000	Ea.	\$	\$
	6" Anchoring Coupling, M.J. (L=18	3")	į.	
23.0499	24.000	Ea.	\$	\$
	24" Retainer Glands, M.J.			
23.0510	24.000	Ea.	\$	\$
	12" Retainer Glands, M.J.			
23.0530	24.000	Ea.	\$	\$
	6" Retainer Glands, M.J.			
23.0661	1.000	Ea.	\$	\$
	8" Plug, M.J.			
23.0660	5.000	Ea.	\$	\$
	12" Plug, M.J.		l	
23.0665	63.800	C.Y.	\$	\$
	Conc. for Thrust Blocks & Anchora			11
23.0670	2,425.000	Lb.	\$	\$
	Reinf. Stl. for Thrust Blks & Ancho			

Item Num	ber Quantity	Unit		Unit Price	Extension
23.0540	4.000	Ea.	\$		\$
******************	24" X 45 Deg. Bend, M.J.				
				Section 5 Total:	\$
	Section: 6 Traffic Sign	nals ar	nd Str	eet Lighting Items	•
24.0101	2.000	Ea.	\$		\$
	Remove Traffic Signal, Complete				
24.0110	2,054.000	LF	\$		\$
	Remove Cable				
24.0120	2.000	Ea.	\$		\$
	Remove T.S. Head				
24.0121	2.000	Ea.	\$		\$
	Remove P.S. Head		<b></b>		<u> </u>
50.0001	1.000	Ea.	\$		\$
	Remove Signal Cabinet		<u> </u>		
24.0122	2.000	Ea.	\$		\$
	Remove PPB				***************************************
24.0225	2.000	Ea.	\$		\$
	Relocate Metro Street Name Sign		<u> </u>		
50.0005	20.000	L.F.	\$		\$
	Relocate 6 Pr. Comm. Cable				
50.0005	63.000	L.F.	\$		\$
	Relocate 6 MM		L		
24.0236	9.000	Ea.	\$		\$
	Relocate Traffic Signal Head 1 Wa		<u> </u>		[]
24.0247	1.000	Ea.	\$		\$
	Relocate Luminaire, 250w. HPSV-		Ľ.		<u>'</u>
24.0804	14.000	Ea.	\$		\$
	Pull Box, Type PB-6		<u> </u>		

Item Num	ber Quantity	Unit	Unit Price	Extension
24.0807	15.000 Pull Box Type PB-9	Ea.	\$	\$
24.0810	38.000 Pull Box, Type FOR27	Ea.	\$	\$
24.0894	55.000 Conduit Bored In Place, 1-1/2"	LF	\$	\$
24.0899	396.000 Conduit Bored In Place, 4 inch "H	L.F	\$	\$
24.0900	77.000 Conduit In Trench, 1/2 Inch	L.F	\$	\$
24.0903	14,425.000 Conduit in Trench, 1-1/2 Inch	L.F.	\$	\$
24.0904	4,191.000 Conduit in Trench, 2 Inch	L.F.	\$	\$
24.0905	176.000 Conduit in Trench, 3 Inch	L.F.	\$	\$
24.0906	12,131.000 Conduit in Trench, 4 Inch	L.F.	\$	\$
24.0914	246.000 Coaxial Cable	L.F	\$	\$
24.0991	246.000 Camera Control Cable	L.F	\$	\$
24.0992	1,588.000 Emergency Detector Cable	L.F	\$	\$
24.0994	1,846.000 Camera Detector Cable	L.F.	\$	\$
24.1001	3,332.000 Traffic Signal Cable, 2 Conductor	L.F.	\$	\$

Item Num	per Quantity	Unit	Unit Price	Extension \$	
24.1002	1,163.000	L.F.			
	Traffic Signal Cable, 3 Conductor				
24.1005	1,332.000	L.F.	\$	\$	
	Traffic Signal Cable, 7 Conductor				
24.1016	514.000	L.F.	\$	\$	
	Traffic Signal Cable, 16 Conductor	r			
24.1020	1,332.000	L.F.	\$	\$	
	Traffic Signal Cable, 20 Conductor	r			
24.1040	9,803.000	L.F	\$	\$	
	Detector Lead-In Cable, 2/Conductor				
24.1046	5,433.000	L.F	\$	\$	
	Fiber Multimode Cable,12				
24.1050	23,066.000	L.F	\$	\$	
	Tracer Wire				
24.1054	836.000	L,F.	\$	\$	
	Service Cable No. 6 USE				
24.1064	369.000	L.F.	\$	\$	
	Circuit Ground, No.6 USE				
24.1065	15,793.000	L.F.	\$	\$	
	Circuit Ground, No. 8 USE				
24.1072	738.000	L.F.	\$	\$	
	Street Light Cable, No. 4 USE in Conduit				
24.1073	30,586.000	L.F.	\$	\$	
	Street Light Cable, No. 6 USE In C	onduit			
24.1194	11.000	Ea.	\$	\$	
	Detector, Vehicle Magnetic				
24.1380	10.000	Ea.	\$	\$	
	Ground Rod, 10'				

Item Numl	per Quantity	Unit	Unit Price	Extension		
24.1469	54.000	Ea.	\$	\$		
	Street Light Pole, Type SL-A-C-45	5-12T-5	i-0.25			
24.1472	2.000	Ea.	\$	\$		
	Street Light Pole, Type SL-A-PI-4	5-12T-	5-0.25			
24.1508	11.000	Ea.	\$	\$		
	Luminaire, 250W HPSV-PC					
24.1507	6.000	Ea.	\$	\$		
	Luminaire, 150W HPSV-PC					
24.1692	31.000	Ea.	\$	\$		
	Detector, Vehicle 4 Turns UC					
24.5219	2.000	Ea.	\$	\$		
	Install Mast Arm Pole Type MA-2					
24.5222	7.000	Ea.	\$	\$		
	Install Mast Arm Pole, Type MA2 (Arm > 50')					
50.0001	6.000	Ea.	\$	\$		
	Install Mast Arm Pole, Type MA2, Arm	(Arm >	50'), Less Traffic Mas			
50.0001	2.000	Ea.	\$	\$		
	Install Mast Arm Pole, Type MA2,					
24.5801		Ea.	\$	\$		
	Install Traffic Signal, Type TS-1, T					
24.5803	21.000	Ea.	\$	\$		
	Install Traffic Signal, Type TS-1, T	36				
24.5807	4.000	Ea.	\$	\$		
************************	Install Traffic Signal, Type TS-1LL	, T51B		and the second s		
24.5808	6.000	Ea.	\$	\$		
	Install Traffic Signal, Type TS-1RR	R, T52				
24.5821	18.000	Ea.	\$	\$		
	Install Pedestrian Signal, Type PS	-1, T13				

Item Num	ber Quantity	Unit	Unit Price	Extension	
24.6011	3.000	Ea.	\$	\$	
	Install Signal Cabinet, Type C				
24.6020	10.000	Ea.	\$	\$	
	Locate Stick				
24.6102	18.000	Ea.	\$	\$	
	Install Pedestrian Push button				
24.6199	12.000	Ea.	\$	\$	
	Install & Adjust Detector Camera		No.	<del></del>	
24.6204	9.000	Ea.	\$	\$	
	Install and Adjust Emergency Receiver				
24.6206	2.000	Ea.	\$	\$	
	Install Traffic Monitoring Camera				
50.0001	1.000	Ea.	\$	\$	
	Remove MA2, Complete				
50.0001	1.000	Ea.	\$	\$	
	Remove Traffic Mast Arm			J	
50.0001	4.000	L.F	\$	\$	
	Remove Detector Cable			<b>-</b>	
50.0001	11.000	Ea.	\$	\$	
	Street Light Pole, Type SL-EM-S-45-12T-5-0.25				
50.0001	1.000	Ea.	\$	\$	
	Install Traffic Mast (Arm > 50')				
50.0001	2.000	Ea.	\$	\$	
	Install Fiber Junction Cabinet				
24.6201	8.000	Ea.	\$	] \$	
	Install Metro Street Name Sign				
			Section 6 Total	: \$	
			Estimate Total	: \$	