



### Stream Segment 10 Components

Perpetuate existing detention ponds near 12+00 for water quantity and quality management

Protect tributary confluence near 16+00, 26+00

Establish floodplain from 0+00 to 39+00, reestablish riparian vegetation from 0+00 to 11+00

Maintain existing detention pond near 34+00 for water quantity management

Construct water quality wetland at existing detention pond near 23+00  
See FIGURE SG2-CD2

Establish right-of-way from 0+00 to 39+00 for management access

